

Massachusetts Cultural Resource Information System

Scanned Record Cover Page

Inventory No:	LAN.900
Historic Name:	Ponakin Bridge
Common Name:	
Address:	
City/Town:	Lancaster
Village/Neighborhood:	Ponakin Mill Village
Local No:	
Year Constructed:	
Architect(s):	
Architectural Style(s):	
Use(s):	Other Transportation
Significance:	Engineering; Transportation
Area(s):	LAN.A: North Main Street - Ballard Hill Area
Designation(s):	Nat'l Register Individual Property (9/10/1979)



The Massachusetts Historical Commission (MHC) has converted this paper record to digital format as part of ongoing projects to scan records of the Inventory of Historic Assets of the Commonwealth and National Register of Historic Places nominations for Massachusetts. Efforts are ongoing and not all inventory or National Register records related to this resource may be available in digital format at this time.

The MACRIS database and scanned files are highly dynamic; new information is added daily and both database records and related scanned files may be updated as new information is incorporated into MHC files. Users should note that there may be a considerable lag time between the receipt of new or updated records by MHC and the appearance of related information in MACRIS. Users should also note that not all source materials for the MACRIS database are made available as scanned images. Users may consult the records, files and maps available in MHC's public research area at its offices at the State Archives Building, 220 Morrissey Boulevard, Boston, open M-F, 9-5.

Users of this digital material acknowledge that they have read and understood the MACRIS Information and Disclaimer (<http://mhc-macris.net/macrisdisclaimer.htm>)

Data available via the MACRIS web interface, and associated scanned files are for information purposes only. THE ACT OF CHECKING THIS DATABASE AND ASSOCIATED SCANNED FILES DOES NOT SUBSTITUTE FOR COMPLIANCE WITH APPLICABLE LOCAL, STATE OR FEDERAL LAWS AND REGULATIONS. IF YOU ARE REPRESENTING A DEVELOPER AND/OR A PROPOSED PROJECT THAT WILL REQUIRE A PERMIT, LICENSE OR FUNDING FROM ANY STATE OR FEDERAL AGENCY YOU MUST SUBMIT A PROJECT NOTIFICATION FORM TO MHC FOR MHC'S REVIEW AND COMMENT. You can obtain a copy of a PNF through the MHC web site (www.sec.state.ma.us/mhc) under the subject heading "MHC Forms."

Commonwealth of Massachusetts
Massachusetts Historical Commission
220 Morrissey Boulevard, Boston, Massachusetts 02125
www.sec.state.ma.us/mhc

This file was accessed on:

Friday, March 07, 2014 at 3:23: AM

MASSACHUSETTS HISTORIC BRIDGE INVENTORY

Municipality: Lancaster District: 3Street name/Rt. #: Ponakin Rd.Over
Street name/Rt. #: N. Naohua RiverBridge key #: TWN 324 008 100 Photo ##s: 42:7A-19A, 70:24-31, 74:1A-2ABridge plan #: L-2-8Common/historic name: Ponakin Bridge

Current owner: _____

UTM coordinates: _____ AASHTO rating: 320 (8-11-88)*****
National Register status (insert date) Field rating:Entered: 9-10-79 Potential: _____

Eligible: _____ Non-eligible: _____

Date built (source): 1871 (NR nomination)

Date(s) rebuilt (source): _____

Builder (source): Watson Manufacturing Co. (NR nomination)

Designer (source): _____

Structural type/materials: 910

pin-connected, wrought- and cast-iron, Post through truss, mildly skewed. 9 full and 2 half (end) panels on the loaded (lower) chord. Cast-iron upper chord in panel-length segments. Eyebar lower chord in interior panels; end panels have wider iron bars stiffened by stay bolts. Verticals are built-up -- I sections (rolled) with cover plates riveted to flanges. Outer diagonals are die-forged eyebars; counters are adjustable rods. Rolled I-beam floor beams are hung from lower chord pins (peculiar hangers). Rolled I-beam upper lateral struts, connected to the chords by bolted castings. Threaded-end rod upper and lower lateral bracing. Vertical end posts pinned*

Overall length: 101' Deck width/layout: 19.7' out-outSkew: ≈ 5° ?Main unit, # spans: 1 lengths: 100'Approaches, # spans: - lengths: -Plaque: Gone location: -

Alterations, unusual features, comments:

- * at lower ends to cast-iron pedestals. Cast-iron joint blocks at each panel point in upper chord. Dry-laid, large-block, roughly squared granite abutments, rough coursed. Present bridge deck has 1 layer of plank on 2 layers of timber stringers. Some damage and deterioration, but no obvious alterations of trusses.

Visual quality (bridge and setting): High____ Average X Low____

Site integrity: Retained____ Violated X

Describe: Riverbanks by bridge are now heavily overgrown, and largely cover the foundations of the former Ponakin Mill, located just upstream to NW.

History of bridge and site:

[see attached copy of the Ponakin Bridge National Register nomination]

The Ponakin Bridge incorporates all 4 specific features which were claimed by Oimeon S. Post in his 1863 patent (#38910). The intent of Post's patent was to improve the design and construction of iron truss bridges "in such a manner as that the expansion and contraction of the material will not produce injurious effects upon the structure, and in this manner obviating one of the most serious objections to the universal use of such bridges." Post's patented features were all focused upon the trusses' joints, and were all designed to allow the upper and lower chords to expand and contract without inducing any additional stresses in the truss web members. Post did not patent the inclined truss verticals which came to be the hallmark of the Post truss -- the verticals in Post's 1863 patent drawings were, in fact, vertical, and of a peculiar double-tapered form (probably meant to be executed in cast iron). The inclined verticals seem to have been a slightly later refinement of Post's original design, and were first used in a bridge erected in 1865.

Sources: E.T. Durfee / P+L. Farnsworth, Ponakin Bridge National Register nomination, 6/29/79
D.H. ✓ United States Patent # 38910.

Summary statement of significance:

The only Post through truss bridge in the MDPW data base; one of only 2 Post or Post-type bridges of any configuration in the MDPW data base. Believed to be the only surviving pure Post through truss bridge in the United States. Trusses appear to be unaltered.

The Post was a significant truss design, used for numerous major long-span bridges in the period 1865-1880. The Ponakin Bridge incorporates all of the features patented by Oimeon S. Post in 1863 (the upper chord "joint boxes," the "cylindrical joints," and the "slotted chords" -- see US Patent # 38910) as well as the inclined truss verticals (which Post did not patent) which are the most visible characteristics of a typical Post truss design.

The last known surviving pure example of a major truss bridge type -- the Ponakin Bridge is of national significance.

Tied (with D-12-20/W-12-1 in Dudley/Webster) as the 3rd-oldest known metal truss bridge in the current MDPW data base.

Statement prepared by: S.J. Roper, MDPW Historic Bridge Specialist Date: 24 Aug. 1989

Field survey by: S.J. Roper, MDPW Historic Bridge Specialist Date: 7/24/85
8/14/86

BRIDGES PREVIOUSLY REVIEWED BY M.H.C. -- CONCURRENCE REAFFIRMED

	<u>Municipality</u>	<u>On/Over</u>	<u>Br. Dept. No.</u>
Bridge:	<u>Lancaster</u>	<u>Ponakin Rd./Naohua R.</u>	<u>L-2-8</u>

has previously been reviewed by the Massachusetts Historical Commission and was ~~determined to be~~ entered in the National Register on 9/10/79.

After a review of all known bridges of comparable structural type identified in the M.D.P.W. statewide computerized database, the M.D.P.W. now reaffirms its concurrence with that initial determination.

Summary statement of significance:

This is believed to be the only surviving pure Post through truss bridge in the United States. The Post was a significant truss type, used for numerous major long-span bridges in the period 1865 - 1880. The Ponakin Bridge incorporates all of the features specifically patented by Simeon S. Post in 1863 (the "joint box" at the upper chord panel points, the "cylindrical joints," the "plotted chord" -- see US Patent 38910) as well as the inclined truss verticals (which Post did not patent) which are the most visible characteristics of a typical Post truss design.

This is a bridge of national significance.

Statement prepared by: S. J. Roper, MDPW Historic Bridge Specialist

Date: 24 August 1989

278

6669 II SW
(SHIRLEY)

280

40'

282 560 000 FEET





FROM SE



FROM NE




FROM SW



UPPER CHORDS + LATERAL SYSTEM FROM NE END
OF SE TRUSS, LOOKING SW

7-24-85



NW TRUSS FROM E



NW TRUSS FROM SW




FROM NE ABUT. LOOKING SW

7-24-85



NE END OF NW TRUSS, FROM SE
(7-24-85)



NW TRUSS, INTERMEDIATE UPPER PANEL POINT (7-24-85)



SE TRUSS UPPER CHORD PANEL POINT, FROM BELOW
(8-14-86)



EAST END POST OF SE TRUSS



(SAME)



LOWER CHORD PANEL POINT FROM
ABOVE

8-14-86



SE TRUSS, 1ST INTERMEDIATE LOWER CHORD PANEL
POINT FROM E END (8-14-86)




SE TRUSS, 2ND INTERMEDIATE PANEL POINT FROM E END
(8-14-86)



SE TRUSS, SW END, 1ST LOWER
PANEL POINT (7-24-85)




SE TRUSS, UPPER CHORD LATERAL
CONNECTION (7-24-85)



(SAME) FROM NE (7-24-85)



UPPER CHORD PANEL POINT (8-14-86)



SE TRUSS LOWER CHORD PANEL POINT FROM
ABOVE (8-14-86)

LAN. 900

900

TO: BETSY FRIEDBERG

RETURN TO REVIEWER BY

(DATE)

FROM: WM. SMITHDATE: 12/10/90TOWN: LANCASTERPROPERTY: L-2-8 Ponankin Rd over Nashua River
(NAME AND ADDRESS)NRIND
9/10/79P1 - PONANKIN
USGS - CLINTON

1. Does this property meet the criteria for NR eligibility?

☒ YES determined elig. site on place on the N.R. 9/10/79☐ NO

A. Criteria

- a. events
- b. lives
- c. characteristics
- d. information

B. Local

State

National

☒ significance

2. Statement of Significance: OR Why not eligible?

1871 Post-trussonly known surviving pure post-truss in
United StatesRecorded summer 1990 by the HARE team
during the Mass Bridge Recording project☐ DOE LETTER WRITTEN

FILED IN ER FILE

(DATE)

Potential district located northwest of
bridge along Ponankin Rd, associated with
mill site near bridge.

MV 2/6/91

1891 Six span steel Pennsylvania through truss. Oldest of the five known Pennsylvania through trusses and is one of the earliest known steel bridges in Massachusetts. Designed by Edward Shaw and built by the R.F. Hawkins iron works.

Dalton

D-1-11

Holiday Road over Wahconah Brook

1894 One span Ball Queenpost pony truss. One of only two surviving examples of Charles Ball unique patented pipe truss bridge. Previously reviewed by the Massachusetts Historical Commission and determined eligible 10/6/81.

Erving/Montague

E-10-3/M-28-0

Central Vermont Railroad
over Millers River,
Newton Street

1905 Five span pin-connected Pratt deck truss. Impressive example of a pin-connected long span deck truss which was favored by American railroads in the 19th century. Bridge is eligible individually and as a contributing element to a potential National Register District.

Framingham

F-7-5

Main Street over Sudbury River

1878 Rare wrought iron bowstring arch pony truss. It is the only known surviving bowstring metal arch in the Massachusetts Department of Public Works database. It is one of six surviving metal truss bridges in the MDPW database built prior to 1880.

Holyoke/South Hadley

H-21-1/S-18-4

State 116/Bridge Street
over Connecticut River

1889 Ten spans wrought iron lattice through truss. A landmark bridge, which is the oldest metal lattice through truss in Massachusetts. It is the only known truss bridge to have ten spans. Bridge was determined to be eligible for the National Register 1/9/79.

Lancaster

L-2-4

Bolton Road over Nashua River

1870 Pinned and bolted wrought iron and cast iron Post's type pony truss. Very early and unique metal truss bridge with national significance entered in the National Register of Historic Places 9/10/79.

Lancaster

L-2-8

Ponakin Road over Nashua River

1871 Post truss. This bridge is the only known surviving Post truss in the United States. This nationally significant bridge is located near a potential historic district.

Lowell

L-15-8

Hale Street over B & M Railroad

1892 One span pin-connected wrought iron Pennsylvania through truss. Early example of an uncommon bridge type in Massachusetts. Only one of the five Pennsylvania trusses to be pin-connected, virtually unaltered. This bridge is also located near the South Common National Register Historic District.



March 6, 1991

Mr. Anthony J. Fusco
Division Administrator
Federal Highway Administration
Transportation Systems Center
55 Broadway - 10th Floor
Cambridge, MA 02142

ATTN: Mr. H. Pearlman

RE: Massachusetts Bridges, National Register Eligibility

Dear Mr. Fusco:

The Massachusetts Historical Commission has reviewed the historic bridge inventory forms prepared by the Massachusetts Department of Public Works. The Massachusetts Historical Commission concurs with the preliminary findings of Massachusetts Department of Public Works that the following bridges meet criteria for listing in the National Register of Historic Places.

Bourne (Bourne Bridge) B-17-4 State 28 over Cape Cod Canal

1934 Three span continuous truss with deck/through riveted steel truss, Warren type truss web. Central span is arched, and highway deck is suspended from its lower chords. Two single intersection Warren deck truss approach spans at each end of the main structure. A landmark, award winning bridge, known internationally for its design and setting.

Bourne (Sagamore Bridge) B-17-5 U.S. 6 over Cape Cod Canal

1935 Three span continuous truss. It is virtually identical to the Bourne Bridge, without the approach spans. The bridge won Honorable Mention in 1935 for its graceful design. Both bridges are elements in a much larger engineering project of significance in its own right, the Cape Cod Canal, a potential National Register Historic District.

Page 1 of 5

Lowell

L-15-19

Bridge Street over Merrimack River

- 1937 Three span cantilever Warren type through truss. This visual landmark is a rare example of a major structural type in Massachusetts. Adjacent to the Locks and Canals Historic District (NR, NHL).

Lowell

L-15-21

Textile Avenue over Northern Canal,
Merrimack River

- 1896 Three span pinned steel Pratt deck truss. Oldest example of an uncommon highway bridge type in Massachusetts. It spans over the Northern Canal and Great River Wall of the Locks and Canals National Register Historic District.

Montague

M-28-18

Bridge Street over B & M Railroad/
C.V. Railroad

- 1897 Latticed type through truss designed by Edge Moor Bridge Company of Delaware. It is the only known example of this unique bridge type..

Northfield

N-22-2

East Northfield Road over
Connecticut River

- 1901-1903 Three span steel Pennsylvania through truss. Unique variation of an uncommon bridge type. Gracefully designed bridge in an outstanding natural setting. The bridge is designed to function as a continuous truss under live loads and a simple truss with cantilevered ends under dead load.

Stockbridge

S-26-3

Butler Road over Housatonic River

- 1881 Pin connected wrought iron half through Pratt pony truss with Borneman type stone pedestals rising above abutments. A rare and unique bridge design by a world famous bridge designer - George Morison. Bridge has national significance.

Waltham

W-4-9

B & M Railroad over State Rte. 60,
Linden Street

- 1894 Steel lattice through truss with quad web system. Intact example of an uncommon bridge type severely skewed. Reviewed and entered in the National Register of Historic Places 9/28/89.

Windsor

W-41-11

Windsor Bush Road over Phelps Brook

- 1893 One span iron and steel Ball Queen post. One of only two surviving examples of Charles Ball unique pipe truss bridge.

The following bridge does not appear to meet National Register criteria at present. However, as this bridge reaches 50 years of age, its National Register eligibility should be reassessed.

LAN. 900

Boston/Chelsea B-16-17/C-9-6 United States Route 1 over Mystic River

1950 Three span cantilever Warren type web through truss. Double deck bridge is a Boston landmark.

Montgomery/Russell M-30-8/R-13-18 I90 over U.S. Route 20, Westfield River

1957 Eight span, two continuous span riveted steel Pratt deck truss. A landmark bridge and the only Pratt deck truss to be designed with continuous deck truss spans.

The following bridges did not appear to meet National Register criteria for individual listing. However, the bridges are within, or adjacent to an historic district or potentially eligible historic district, and plans for replacement should take into consideration potential impact to adjacent properties.

Fitchburg F-4-12 State Rte. 31/Rollstone Street over North Nashua River, Broad Street

This bridge is located adjacent to lower Rollstone Bridge (1870 Parker pony truss).

Greenfield/Montague G-12-20/M-28-1 Montague City Road over Connecticut River

This bridge stands between East Greenfield and Montague city. Though inventory is incomplete, significant historic resources are in both areas. There is a group of turn of the century cottages on Montague City Road that may be eligible for listing in the National Register.

Lawrence L-4-24 Salem Street over B & M Railroad

This bridge is adjacent to mill building and Victorian Gothic church; however, the level of information on this area is not well documented at this time.

The MHC concurs with the preliminary findings of MDPW that the following bridges do not appear to meet criteria for listing in the National Register of Historic Places.

Amesbury/Newburyport A-7-16/N-11-17 I-95 over Merrimack River

Boston/Quincy B-16-368/Q-1-50 Long Island Bridge over Quincy Bay
Conway C-20-7 Hickory Ridge Road over South River
Erving/Montague E-10-5/M-28-5 Paper Mill Road over Millers River
Montague M-28-20 C.V.R.R. over North Leverett Road/
Sawmill River
Northfield N-22-26 B & M Railroad over Caldwell Road/
Connecticut River
Westfield W-25-4 United States Route 20 over
Westfield River

LAN.900

If you have any questions, please feel free to contact William Smith of this office.

Sincerely,

Judith B. McDonough

Judith B. McDonough
Executive Director
State Historic Preservation Officer
Massachusetts Historical Commission

JBM/WS/kab

cc: Frank Bracaglia, MDPW

5/72

(Attach photo here)

LAN. 900

NR

900

FORM F - STRUCTURES

2. Town Lancaster

MASSACHUSETTS HISTORICAL COMMISSION
Office of the Secretary, State House
Boston 02133

Location Ponakin RoadOwner Town of Lancaster

1. Category

☒ BridgeDate 1871

Canal

Pound

Tower

Abijah P. Marvin's History

Dam

Street/road

Source of date of Lancaster, 1879

Fort/fortification

Vehicle

Original owner Town of Lancaster

Gate

Vessel

Designer Unknown

Kiln

Wall/fence

Light

Windmill

Powder house

Other

Available to public Yes3. Condition GoodPresent use Bridge4. Type IronDimensions 20' wide x 100' longConstruction material Iron with wood planking and granite block foundation5. Setting Rural, country road, with no other structures close by.

6. History (continue on reverse side)

The earlier wooden Ponakin Bridges caused considerable yearly expense, as they required constant repair. In times of heavy rains and spring flooding, the bridge would be washed away and have to be replaced. Yearly inspectors were named for each bridge and in 1803 John Maynard was chosen for Ponakin. When a bridge washed away, committees were formed to rebuild them. In 1839, it was voted to rebuild the Ponakin, and the cost was \$568.19. The next year, it again washed away and \$1,200.00 was voted to make it permanent. The cost exceeded this amount and came to \$1,407.31.

In 1870, the town adapted the plan of building iron bridges. The first to be built in Lancaster was the Atherton Bridge. In 1871, a vote was passed to rebuild Ponakin using iron. The committee was George A. Parker, Calvin Holman, and John Cunningham. Appropriation for 1871 for bridges was \$12,000 and Ponakin took \$5,981.21 of this sum. In 1952 it was voted to raise and appropriate the sum of \$1,500 for replanking and general repairs. In 1961 was voted the sum of \$4,500 to repair the bridge. (Continued)

7. Indicate location of structure in relation to cross sts., other structures or permanent points of reference.

Footage of structure from street (on the street)Recorder Janice Breen, SecretaryFor Lancaster Historical CommissionPhoto attached Date June 24, 1975

SEE REVERSE SIDE

RECEIVED

JUN 27 1975

MASS. HIST. COMM.

Clinton 22

LAN.900

7. History, cont.

The Ponakin Bridge was significant to the many people who worked at the nearby (now gone) Ponakin Mill which operated from mid-18th Century until its closing in 1927.

"Just below and along the river bank lies the Ponakin Village where the mill hands have their homes, and their farms and their gardens, the mill itself and the bridge which spans the river. The old records speak often of the travels of this bridge and of a new bridge being built after each spring flood", says a newspaper clipping of 1927.

8. Bibliography

Town Records:

Highway Minutes (1900-1912)

Town Clerks Records 1952 and 1961

Selectmen's Expenditures (1836-1905), 1837, 1838, 1840, (1888-1900)

Abijah P. Marvin, History of Lancaster 1642-1879, Lancaster 1879.

RESTRICTIONS

Deed Information: Book number _____ Page _____, Registry of Deeds

5/72

(Attach photo here)

LAN. 400

FORM F - STRUCTURES

MASSACHUSETTS HISTORICAL COMMISSION
Office of the Secretary, State House
Boston 02133

2. Town LancasterLocation Ponakin RoadOwner Town of LancasterDate 1871Source of date Abijah P. Marvin's History of Lancaster, 1879Original owner Town of LancasterDesigner UnknownAvailable to public Yes

1. Category

<input checked="" type="checkbox"/> Bridge	Pound
Canal	Tower
Dam	Street/road
Fort/fortification	Vehicle
Gate	Vessel
Kiln	Wall/fence
Light	Windmill
Powder house	Other

3. Condition GoodPresent use Bridge4. Type IronDimensions 20' wide X 100' longConstruction material Iron with wood planking and granite block foundation5. Setting Rural, country road, with no other structures close by.

6. History (continue on reverse side)

The earlier wooden Ponakin Bridges caused considerable yearly expense, as they required constant repair. In times of heavy rains and spring flooding, the bridge would be washed away and have to be replaced. Yearly inspectors were named for each bridge and in 1803 John Maynard was chosen for Ponakin. When a bridge washed away, committees were formed to rebuild them. In 1839, it was voted to rebuild the Ponakin, and the cost was \$568.19. The next year, it again washed away and \$1,200 was voted to make it permanent. The cost exceeded this amount and came to \$1,407.31

In 1870, the town adapted the plan of building iron bridges. The first to be built in Lancaster was the Atherton Bridge. In 1871, a vote was passed to rebuild Ponakin using iron. The committee was George A. Parker, Calvin Holman, and John Cunningham. Appropriation for 1871 for bridges was \$12,000 and Ponakin took \$5,981.21 of this sum. In 1952 it was voted to raise and appropriate the sum of \$1,500 for replanking and general repairs. In 1961 was voted the sum of \$4,500 to repair the bridge. (Continued)


7. Indicate location of structure in relation to cross sts., other structures or permanent points of reference.

Footage of structure from street (on the street)

Recorder Janice Breen
For Janice Breen, Secretary
Lancaster Historical Commission

Photo attached Date June 24, 1975

SEE REVERSE SIDE



Ponakin Road Bridge
Spanning North Branch of Nashua River
on Ponakin Road
Lancaster Vicinity, Massachusetts
Worcester County

HAER No. MA-13

PHOTOGRAPHS

WRITTEN HISTORICAL AND DESCRIPTIVE DATA

Historic American Engineering Record
National Park Service
Department of the Interior
Washington, D.C. 20240

HISTORIC AMERICAN ENGINEERING RECORD

PONAKIN ROAD BRIDGE

DATE: 1871

LOCATION: Spanning North Branch of Nashua River
on Ponakin Road
Lancaster Vicinity, Massachusetts,
Worcester County

DESIGNED BY: Simeon S. Post

BUILT BY: Watson Manufacturing Co.,
Paterson, New Jersey

OWNER: Town of Lancaster

SIGNIFICANCE: The single span Ponakin Road Bridge is 100 feet long and 20 feet wide, with vertical end posts. The bridge has diagonal compression members and diagonal eye-bar tension members that extend two panels, with secondary tension rods extending over one panel. The upper chord lateral bracing is riveted and additional bracing is provided by diagonal cross bars. This truss was developed by Simeon S. Post in about 1865, with a configuration characterised by compression members inclining towards the center of the bridge. The post truss was an important bridge form in the second half of the 19th century, and widely used for transcontinental railway construction. The Ponakin Road Bridge is the only all metal Post truss bridge surviving in the U.S.

This type of bridge is commonly referred to as the Post Patent Truss, but research in the Patent Office records failed to uncover any patents taken out by S.S. Post that describe a truss with inclined compression members. Nevertheless, this type of truss was widely known as the Post truss and it was built in great profusion throughout the East and Midwest between 1865 and 1880. After this time its popularity waned as the standardized Pratt truss began being built in great numbers. The Ponakin Road Bridge is listed on the National Register of Historic Places.

RESEARCH AND
TRANSMITTAL BY: Donald C. Jackson, Engineer, and
Monica E. Hawley, Historian, 1983

Addendum to
Ponakin Bridge
Spanning the Nashua River on Ponakin Road
Lancaster
Worcester County
Massachusetts

HAER No. MA-13

PHOTOGRAPHS
REDUCED COPIES OF MEASURED DRAWINGS
WRITTEN HISTORICAL AND DESCRIPTIVE DATA

Historic American Engineering Record
National Park Service
Department of the Interior
Washington, DC 20013-7127

HISTORIC AMERICAN ENGINEERING RECORD

PONAKIN BRIDGE
HAER No. MA-13

Location: Spanning the North Nashua River on Ponakin Road, Lancaster, Worcester County, Massachusetts
UTM: Hudson, Mass., Quad. 19/279240/4706480

Date of Construction: 1871

Structural Type: Wrought- and cast-iron Post-patent through truss bridge

Engineer: Unknown; design based on 1863 patent by Simeon S. Post

Fabricator/
Builder: Watson Manufacturing Company, Paterson, New Jersey

Owner: Town of Lancaster, Massachusetts

Previous Use: Rural vehicular and pedestrian bridge

Present Use: Closed to vehicular traffic, 1978

Significance: The Ponakin Bridge is the only known surviving iron bridge to incorporate all of the design features of Simeon S. Post's patent for an "improved iron truss bridge." Post trusses enjoyed a brief period of popularity in the late 1860s and early 1870s. Railroads often chose Post's bridge for long-span river crossings. The Ponakin Bridge is an unusual example of a Post truss used for a relatively short-span highway bridge. The Ponakin Bridge served a small cotton manufacturing village on the west bank of the North Nashua River. The bridge has sustained some structural damage but has not been significantly altered.

Project Information: Documentation of the Ponakin Bridge is part of the Massachusetts Historic Bridge Recording Project, conducted during the summer of 1990 under the co-sponsorship of HABS/HAER and the Massachusetts Department of Public Works, in cooperation with the Massachusetts Historical Commission.

Patrick Harshbarger, HAER Historian, August 1990

PONAKIN BRIDGE
HAER No. MA-13
(page 2)

Introduction

The Post truss, although never as prevalent as its nineteenth-century counterparts--the Howe, Warren and Pratt trusses--nonetheless played a definitive role in the development of American bridge building. Designed by Civil Engineer Simeon S. Post (1805-1872), the truss enjoyed a brief period of popularity in the late 1860s and early 1870s, primarily for long-span railroad bridges. Post never patented the web configuration of the truss, but in 1863 he received a patent for the joint connections. Engineers considered Post's design ideal because of its apparent stiffness and economy of material. Nevertheless, a number of factors, including heavier load requirements, led to the obsolescence of the Post truss by the century's last decade.¹

The Atherton Bridge, 1870 (HAER No. MA-17), and the Ponakin Bridge, 1871, both located in Lancaster, Massachusetts, are two of only a small number of surviving examples of Post-type trusses in the United States.² Unlike the majority of Post trusses built in the nineteenth century, the Atherton and Ponakin Bridges are short-span highway bridges, rather than long-span railroad bridges. The two bridges, excellent examples of this now-rare truss type, owe their survival to their location on less-traveled byways of the nineteenth century. Both bridges are listed on the National Register of Historic Places.

Although somewhat similar in form, the Atherton and Ponakin Bridges differ with regard to how closely they follow the Post design and patent. The Ponakin Bridge, built by the Watson Manufacturing Company of Paterson, New Jersey, incorporates all of the features of Post's design. The Atherton Bridge, built by J.H. Cofrode & Company of Philadelphia, adapts the Post-truss configuration to a smaller highway bridge, but does not make use of the specific features of Post's patent.³(See Figure 1.) For more information on the Atherton Bridge, refer to HAER Report No. MA-17.

Description

The Ponakin Bridge spans the North Nashua River at Ponakin Road two miles north of Lancaster Center. The bridge is nestled at the foot of a small valley where the river enters a broad flood plain, about two-and-a-half miles above the confluence of the North Nashua and Nashua Rivers. The ruins of mills (see Figure 2) and an extensive water-power system lie upriver on the west bank, and the banks all around are covered with lush vegetation. Ponakin Road winds off of Massachusetts Route 117 about 200' southwest of the bridge, crosses the river, and rises steeply to the west, then bears to the south through the small village of Ponakin. The bridge has been closed to vehicular traffic since 1978, and the road is blocked with concrete barriers. In addition, guardrails and mesh fencing have been bolted across the bridge's portals to keep out pedestrians and would-be vandals.

The Ponakin bridge is a single-span through truss, measuring 100'-0" long, 14'-9 $\frac{1}{4}$ " high, and 20'-8" wide. The upper chord is comprised of cast-iron, C-shaped beams, each measuring about 10' long, joined together with bolts. The lower chord is comprised of paired, wrought-iron bars, measuring approximately 10' long, joined together by pins. The bridge incorporates the signature of all Post trusses, the pattern and inclination of the posts and diagonals. Generally, the posts incline at about 20 degrees towards the

PONAKIN BRIDGE
HAER No. MA-13
(page 3)

center of the bridge, and the diagonals incline at about 45 degrees towards the bridge abutments. In the Ponakin Bridge, the posts are made from I-shaped iron beams with reinforcing plates riveted to the top and bottom. The diagonals are wrought-iron bars varying in width from 1" at the center of the bridge, to 2" at the ends of the bridge. The diagonals of a Post truss are double-intersecting, which means they pass through one post between their upper and lower chord connections. The counters, which are 1"-diameter rods with turnbuckles, incline at 45 degrees towards the center of the bridge.

The joints, or the various points where the chords and web members connect, are another distinctive feature of the Ponakin Bridge. Each footing, where the endpost meets the lower chord, is encased inside a cast-iron box with a flared pedestal resting on the abutment. A pin passes through the box, connecting the endpost to the lower chord. Inside the box, the endpost fits into a rounded casting, and the slotted lower-chord bars rest on either side of the post. Counters attach to the lower chord by means of a bolt near the footings, but these are not encased in the boxes. The upper-chord joints are also held together by means of pins and cast-iron joint boxes. The segments of the upper chord rest directly on top of the joint boxes. Bolts tie together the joints where the lower chord meets the diagonals, posts, and counters. U-shaped hangers, also attached to the bolts, support iron floor beams. Lower lateral rods bolt to the lower chord near the joints. Timber joists or stringers rest on top of the floor beams. A secondary system of wooden joists rests above the stringers and runs the width of the bridge. A wood plank deck sits on top of the secondary joists.

The Ponakin Bridge shows no signs of significant alteration. The only apparent repair has been the periodic replacement of floor joists and decking. The lower chords have buckled about 10' in from the footings and the bridge shows some signs of structural weakness. A 1960 photograph of the bridge shows a builder's plaque that has since been removed. The plaque read: "S.S. Post's Patent, June 16, 1863, Watson Mfg. Co., Builders, Paterson, N.J." (See HAER drawings and photographs.)

Simeon S. Post and the Post-Truss Patent

During the nineteenth century, bridge building evolved from an art to a science; a craft once practiced by local carpenters and millwrights became a business organized by engineers and industrialists. Iron and steel replaced wood as the engineer's material of choice, and monumental bridges spanned rivers at one time thought impassable.

The career of Simeon S. Post reflected this transformation. Born in New Hampshire in 1805, Post did not receive an education in engineering, but rather, learned the trade of a house-joiner. The facts of Post's early life are sketchy, but sometime after completing his apprenticeship he moved to Montpelier, Vermont, to begin his career. While there, he made the acquaintance of the state's Surveyor General, John Johnson, and became involved with surveying for the new state capitol. Johnson, perhaps as a political favor, arranged to have his son, Edwin Johnson, the chief engineer of the newly-formed Auburn & Syracuse Railroad, appoint Post to a resident engineer's position on the railway.⁴

The fledgling railroad industry provided one of the greatest training

PONAKIN BRIDGE
HAER No. MA-13
(page 4)

grounds for civil engineers. A survey of the first fifty-five members of the American Society of Civil Engineers (ASCE), the oldest professional engineering organization in the United States, found that thirty had worked for the railroads and that fully 60 percent had not attended an engineering school. Like Post, they gained their education from the practical experiences of surveying railways, digging tunnels, and erecting bridges.⁵

Although the railroads provided opportunities for ambitious young men, the early history of railroad-bridge engineering was frequently marked by trial-and-error methods, inadequate knowledge of the strength of building materials, and irresponsible construction practices. The railroads required bridges stronger and more durable than the traditional wooden ones built by American craftsmen. Iron offered a solution to the railroads' bridge problem but manufacturing technology limited the size, width and strength of truss members. Engineers poorly understood the factors that determined the maximum load and structural action of iron trusses; consequently, they met with limited successes, and some disastrous failures.⁶

Post was in an ideal position to observe and participate in the development of iron bridge-building technology. In 1840 he became the New York & Erie Railroad's resident engineer, a position that was to bring him in contact with Squire Whipple, one of the most highly-regarded American bridge builders of his day, who also worked for the railroad company. Whipple patented two iron trusses, one in 1841 and the other in 1846, both of which became important models for later bridges. Whipple was also foremost among his American contemporaries in understanding the nature of truss action. His book, A Work on Bridge Building (1847), was the first scientific treatise to accurately describe the way loads distribute themselves through the joints and the separate members of a truss. In the late 1840s, the New York & Erie built a number of Whipple trusses. By that time Post had climbed to the position of Superintendent of Transportation, and may have had some oversight responsibilities for the bridges' construction.⁷

If Post had the good fortune to associate with America's foremost bridge engineer, he also had the bad fortune to experience iron bridge disasters first hand. In 1849 and 1850, the New York & Erie contracted with Nathaniel Rider, a bridge-builder from New York City, to erect several trusses along its lines. Two of the bridges failed, and public outcry convinced officials of the New York & Erie Railroad to suspend the building of new iron bridges and to tear down all of the railroad's existing iron trusses, including those designed by Whipple. Fifteen years passed before the New York & Erie built another iron bridge.⁸

Despite the railroad's bridge problems, Post's career began to earn him the respect and admiration of his peers. Post worked with Ezra Cornell to introduce the earliest-known system of telegraphy to monitor the movement of trains and to prevent collisions. He also invented a parabolic headlight reflector used by locomotives, a system of railroad baggage checks, and a design for railroad timetables widely adopted by other railroad companies. In 1851, after eleven years of employment with the company, the New York & Erie Railroad promoted Post to the position of Chief Engineer.⁹

As his career unfolded, Post took some interest in the development of engineering as a profession. In 1852 Post accepted an invitation to join with eleven other engineers as a founding member of the American Society of Civil

PONAKIN BRIDGE
HAER No. MA-13
(page 5)

Engineers (ASCE) in New York City. The early history of this organization was full of disappointment; meetings were underattended, and one of the association's officers lost the organization's money in a doubtful investment scheme. The organization became viable only after the Civil War. Shortly after gaining his charter membership, Post left the East Coast for a new position with the Ohio & Mississippi Railroad; henceforth, he appeared to take only a passing interest in the ASCE's activities.¹⁰

In 1855 Post returned to the New York & Erie Railroad as a consulting engineer and received charge of the construction of New York's Bergen Tunnel. Three years later, as the project neared completion, funds ran short and Post found himself without a job. Consequently, he set up his own independent civil engineering practice in New York City, and turned his attention to the problems of bridge construction.

Few engineers could have been better prepared to consider the needs of American bridge builders. In 1859, Post published his "Treatise on the Principles of Civil Engineering as Applied to the Construction of Wooden Bridges." The treatise appeared in weekly installments in American Railroad Journal, and was clearly aimed at an audience of railway men uninitiated to calculating loads and strains. Beginning with an explanation of Newtonian forces, and ending with numerous examples of how to determine the correct size and length of wooden truss members, Post demonstrated a clear understanding of Whipple's principles of truss building. (See Appendix A.) Post's decision to apply this knowledge to wooden bridges probably reflected the simple and overwhelming fact that most American railroads still preferred to build out of the less-costly material.¹¹

Still, Post understood that the future of American bridge-building lay in the construction of strong and durable iron trusses. Beginning in the 1860s, many engineers formerly employed by the railroads came to the same conclusion. They struck out on their own into the potentially profitable business of contract iron-bridge building. These entrepreneurs associated themselves with existing firms or organized new companies, often making a specialty of a certain type of truss, sometimes controlled by a patent or license.¹²

In June 1863, Post obtained letters of patent for an improvement in iron bridge joints. (See Appendix B.) He claimed that his method of construction allowed the struts and braces to revolve upon a bolt to the degree that the bridge expanded and contracted from changing load conditions and variations in temperature. Post's patented joints consisted of a joint box and pin that connected segments of the top chord and received the heads of the posts, struts and braces; a cylindrical joint that held the rounded end post; and a slotted chord used in combination with the cylindrical joint. Bridge engineers considered increasing the rigidity of iron trusses while maintaining enough flexibility to keep them from buckling a fundamental problem, and Post attempted to address this concern.¹³

Two years after receiving his patent, Post contracted with his old employer, the New York & Erie Railroad, to build the first bridge based upon his improved design. Post's truss at Washingtonville, New York, was also probably the first iron bridge erected by the railroad since the disasters in 1850. This bridge made use of Post's patented joints and had the distinctive arrangement of inclined posts and diagonals found in his later trusses.

PONAKIN BRIDGE
HAER No. MA-13
(page 6)

During the next five years, Post devoted his time to the construction of his bridges. Unfortunately, the record of these years is vague, and Post's attempts to turn a profit through licensing agreements, partnerships and other business dealings can only be surmised. Apparently, either because of old age, disinterest, or lack of financial resources, Post made no attempt to start his own bridge-building firm, but licensed his patent to the Watson Manufacturing Company of Paterson, New Jersey, of which his son, Andrew Post, was a managing partner. In 1867 the Illinois & St. Louis Bridge Company, which probably also held license to build the patented trusses, listed Post as a consulting engineer.¹⁴ Whether or not Post had relationships with other bridge manufacturers is unknown. It is also unclear what involvement Post had with the construction and engineering of specific bridges.

In March 1870, at the age of 65, Post accepted a position as Engineer of Construction for the Northern Pacific Railroad. Four months later, he was stricken by paralysis, probably from a stroke, and his professional career came to an abrupt end. Post died in Jersey City, New Jersey, on June 29, 1872.¹⁵

The Post Truss in the United States

The Post truss enjoyed a brief, but vigorous, period of popularity in the late 1860s and early 1870s. In 1868 Post's design received national recognition when the Union Pacific Railroad decided to use it for the largest river crossing on its line, spanning the Missouri River between Council Bluffs, Iowa, and Omaha, Nebraska. The Union Pacific's choice was surprising, considering the untested nature of the bridge, but Post's truss claimed greater rigidity under moving loads, and this appealed to the railroads. The Illinois & St. Louis Bridge Company completed this extraordinary bridge in 1872. (See Figure 3.) Including the approaches, it was a little over two-and-a-half miles long, with eleven cast- and wrought-iron Post truss spans measuring 250' each.¹⁶

Not to be outdone by the Union Pacific, other railroads expanding into the west also chose Post trusses for their crossings of the Missouri River. In 1869, the Chicago, Burlington & Quincy Railroad began building a five-span bridge, measuring approximately 1,000' long, at Kansas City, and shortly thereafter, another of nearly the same length at Leavenworth, Kansas. The Post truss reached its maximum length in the Missouri River Bridge of the Missouri, Kansas & Texas Railroad, at Booneville, Missouri, in 1874. This bridge had a swing span 360' long. At least for a short while, the enthusiasm that followed in the wake of the transcontinental railroads secured the popular reputation of the Post truss as a viable option for longer bridge spans.¹⁷

The Post truss belonged to a family of trusses that could be distinguished by posts or verticals in compression, and diagonals in tension. Throughout the mid-nineteenth century countless engineers and bridge-manufacturers built variations on this design, the most common of which was the Pratt truss, but to which the less-common Parker, Camelback, Lenticular, Baltimore, Pennsylvania, Kellogg, Whipple and Post trusses were all related. This impressive list of truss types was the result of experimentation by engineers, and of keen competition among firms searching for advantages

PONAKIN BRIDGE
HAER No. MA-13
(page 7)

against their rivals. Engineering journals constantly featured articles comparing the merits of one truss against another. The Post truss's distinction as a long-span bridge was an important factor in this debate.¹⁸

Not surprisingly, bridge builders found the most attractive feature of the Post truss to be the unusual pattern of inclined posts and verticals, and not the special joints, which Post had thought important enough to patent. Post's patented joints could not be copied except under license from the engineer or his assignees, but the distinctive diagonals and posts held no such restrictions. In 1870 Col. William E. Merrill, an engineering graduate of the United States Military Academy, published a book that claimed that the Post-truss type conformed with his theoretical determinations of the most economical angles for bridge members. Merrill's findings had important implications; he argued that given trusses of equal length, depth, width and strength, the Post truss would contain less metal than other trusses, at a minor, although perhaps not insignificant, cost advantage to its manufacturer.¹⁹ Although Merrill's calculations were somewhat misleading, because many other factors influenced bridge costs, his assertions created a stir in the engineering community.

Whether Merrill had anything to gain by promoting the Post truss over the other types is unknown, but his assertions touched off a fierce debate with Squire Whipple, the dean of American bridge builders. In a paper read before the ASCE in 1872, Whipple, in a scathing tone untypical for engineering journals, told the society's members that Merrill had misrepresented the Whipple Truss and made it appear vastly inferior to the Post Truss. In fact, Whipple concluded, the Post truss was merely a modification of the Whipple truss, "first used and thoroughly discussed" by himself.²⁰

Simeon Post lay dying, and could not answer either Merrill's or Whipple's assertions. Post may have inclined the truss posts for economic reasons, but no historical records have been found to say that Post might not have also felt that his modifications strengthened the truss or offered a technical advantage in the manufacturing process. Whipple directed his attack solely at Merrill, so there was also no reason to believe that Post had fallen out with the well-regarded engineer.²¹

Persuaded by the economy of the Post-truss form, any number of bridge builders may have designed variations on it. The Atherton Bridge (HAER No. MA-17), for example, appears to be an adaptation of the Post truss to a small highway bridge. The Bell's Ford Bridge in Seymour, Indiana, is a composite bridge with wooden posts and iron diagonals. Other Post trusses no longer surviving, but identified from historic photographs, include bridges in Paterson, New Jersey; Pittston, Pennsylvania; Columbiaville, New York; and Clear Creek Canyon, Colorado. How many of these bridges were built by the Watson Manufacturing Company, and other licensees of the Post Patent is unknown.²²

The popularity of the Post truss ended almost as quickly as it began. By 1880, bridge companies had stopped building Post trusses. The last two decades of the nineteenth century saw an increasing uniformity and standardization of truss form, as competition weeded out those trusses that did not demonstrate versatility, durability, and economic desirability. In 1876, the Watson Manufacturing Company erected three Post trusses in Brazil and then went into receivership and out of business. Heavy locomotives and

PONAKIN BRIDGE
HAER No. MA-13
(page 8)

railroad cars simply wore out the cast and wrought-iron, pin-connected bridges. The Union Pacific Railroad replaced its Post-truss Missouri River bridge in 1886, and the other Post-trusses across the Missouri disappeared by the turn of the twentieth century.

The railroads demolished or abandoned the Post trusses at an astonishing rate. Cantilever bridges replaced trusses in long-span crossings, and Pratt and Warren trusses became the engineers' choice for shorter spans. J.A.L. Waddell, an authority on nineteenth and early-twentieth century bridge engineering, remembered being called upon in 1888 to rebuild a large Post truss which had caught fire. He wrote that, "It was a very difficult piece of work to patch up the detailing so as to make it safe and passable; and it was absolutely impossible to make the bridge anything like a first-class structure, even for the light live load it had to carry." Those Post trusses that incorporated the patented joints proved even more difficult to maintain; the cast-iron boxes that encased the joints prevented inspection and repair of pins and bridge members.²³

By the first decades of the twentieth century, even inclined posts and diagonals, once the Post truss's strongest feature, became a weak point in light of advances in the theoretical understanding of structural engineering. The odd angles made it difficult to determine whether compressive or tensile forces would be placed on certain bridge members as live loads passed over the truss. In 1927, George Fillmore Swain, one of the nation's foremost structural engineers and a professor at Harvard University, wrote the engineering professions' final words on the Post truss: "There is nothing to recommend this truss that cannot be obtained in a better and more economical way." Forgotten, ignored and disdained, the Post trusses disappeared from the landscape.²⁴

Early Bridges in Lancaster

The town of Lancaster lies in the rolling hills of the Worcester Plateau in Central Massachusetts, at the confluence of the Nashua and North Nashua Rivers. Founded in 1653, Lancaster became an important early market center and a gateway to the western frontier of New England. By 1771, Lancaster was the region's wealthiest agricultural and commercial town. The fertile fields of the Nashua intervale contributed to the town's prosperity, as did the development of a number of industries, including saw and grist milling, potash making, tanning, slate quarrying, and ceramics manufacturing. As the town's citizens entered the nineteenth century, overland transportation increased in importance. Shortly after the turn-of-the-century, the state chartered the Lancaster-Bolton Turnpike (1806) and the Union Turnpike (1808), as part of an interregional network of east-west roads radiating from Boston and passing through the town of Lancaster.²⁵

Local farmers and millwrights built the town's early bridges, which were usually nothing more than wooden trestles with log abutments. Floods regularly washed away one or more of Lancaster's seven or eight bridges, and the citizens attempted to replace them with a minimum of fuss and expense, although the costs occasionally proved burdensome. In the late-eighteenth century, the town issued lottery tickets in an attempt to raise money for the general repair and rebuilding of the bridges.²⁶

PONAKIN BRIDGE
HAER No. MA-13
(page 9)

New England's tradition of local government gave the town meeting and the elected officials (selectmen) authority over the erection of new bridges. Beginning in the early-nineteenth century, Lancaster's town records show a continuing concern for bridge improvements. In 1801 a town committee recommended building stone arch bridges, but this suggestion does not appear to have been adopted. The town treasurers kept careful expense records, and rarely did a year pass when the town did not pay for some bridge repairs or upkeep.²⁷

Bridges had crossed the North Nashua River at the site of the Ponakin Bridge since the late-seventeenth or early-eighteenth century. The Ponakin Bridge formed part of the Lunenberg Road that connected Lancaster with the town of Lunenburg to the north. The bridge crossed the North Nashua River near an advantageous water power site that had been used for saw and grist milling since the early-eighteenth century. By 1800, a nailmaking and shoeshank operation had also begun operation near the bridge.²⁸

Town reports first mention the Ponakin Bridge in 1810, when a repair of \$16.41 was recorded. The bridge was located at the foot of a swift section of river and was prone to damage from flooding. In 1821, 1829, 1839, and 1840, the Ponakin Bridge washed away, at considerable expense to the town.

The Ponakin Bridge probably remained a simple timber structure until 1840 when local bridge builders decided to erect a Town lattice truss similar to the one constructed ten years earlier at the site of the Atherton Bridge (HAER No. MA-17). The cost of the new structure was \$749.98. The 1840 Town truss survived thirty years, although it occasionally required substantial repairs, costing the town \$343.29 between 1841 and 1866.²⁹

As the nineteenth century progressed, the town of Lancaster ceased to be a major commercial center for the region. Industrialization brought textile mills to the area. The Lancaster Mills Company had been organized in the 1820s, and the town of Clinton, comprised of Irish workers' communities, separated from Lancaster in 1850. Clinton, Fitchburg, and Leominster emerged as new centers of commerce. Lancaster maintained its agricultural economy -- based on supplying the Boston market with livestock, dairy products, corn, hops, potatoes and hay--and experienced some growth in the industrial areas, primarily cotton spinning, expanding from a annual production rate in 1845 of 135,000 yards to a rate in 1865 of 500,000 yards. In 1861, a cotton mill opened on the west bank of the North Nashua River opposite the Ponakin Bridge.

Following the Civil War, Lancaster, a short day's train ride from Boston, also became a popular summer residence for wealthy merchants and industrialists.³⁰ One of the most prominent of these prosperous summer tenants was Nathaniel Thayer, a Boston financier and philanthropist with roots in Lancaster. In 1870, Thayer (age 62), claimed permanent residence in Lancaster as a means of escaping Boston's high tax rates. The town of Lancaster suddenly received a tax windfall of over \$12,000 on Thayer's estimated \$1.2 million; this exceeded twenty-five times the amount paid by any other single citizen in town. Lancaster's property owners rejoiced because the tax rates could be easily kept at a relatively modest one percent, and new public improvements could be undertaken with the expanded tax pool.³¹

In the spring of 1870, Lancaster's citizens gathered at the town meeting to decide what to do with their new-found tax dollars. J.S.L. Thompson, the town clerk, recorded that a proposal to replace the wooden bridges with iron

PONAKIN BRIDGE
HAER No. MA-13
(page 10)

and to improve the principal roads received a favorable hearing. The first bridge on the town's agenda was the Atherton Bridge (HAER No. MA-17), and the town appointed a bridge committee of five members to look into the cost of buying a new iron truss for that location. The Atherton Bridge, a unique variation of a Post truss, was erected that summer by J.H. Cofrode & Company of Philadelphia.

In the spring of 1871, Lancaster's citizens gathered once again at the annual town meeting. They reviewed the finances, elected new officials, and discussed needed public improvements. The town clerk wrote in his personal journal that, "the town was so well pleased with the new bridge [Atherton Bridge], that they voted to rebuild with iron, two bridges, vis. the Centre and Ponakin, at an expense of about \$6000 each [sic]." The citizens of Lancaster had quickly shown pride in their new iron bridge, and willingly spent Thayer's tax dollars to upgrade their other bridges.³²

The vote to build the new iron bridges passed unanimously, but the selection of a bridge committee broke into a quarrel. The citizens passed over several members of the Atherton Bridge Committee, including Charles L. Wilder, in favor of three other gentlemen, George A. Parker, Calvin Holman, and John Cunningham. The disagreement might not have mattered greatly except that George A. Parker was a noted engineer who had had previous dealings with Wilder.³³

George A. Parker

Born in 1822, the son of a poor farmer from New Hampshire, Parker had worked his way through school and at a young age attained a position as a draughtsman in an engineering office in Charlestown, Massachusetts. Like so many of his contemporaries, Parker built his career with the railways. In 1849, the Rutland & Burlington Railroad hired Parker to build a bridge across the Connecticut River, which he completed underbudget and in good time. In 1855, Parker became general superintendent of the Philadelphia, Wilmington & Baltimore Railroad, and undertook the bridge project that would earn his national reputation. A bridge across the mouth of the Susquehanna River at Havre de Grace, Maryland, was the last link needed to complete a continuous railway stretching from Washington D.C. to Philadelphia and the northeast. In addition to the height and length of the span, the principle difficulties facing Parker were the unstable nature of the river bottom, the unusual depth of the water, and the problems of flooding and ice packs. The financial crisis of 1857 brought a five-year stoppage to the project and during this time Parker moved his family to Lancaster where his father had for some years owned a farm. In 1862 the Susquehanna River Bridge construction resumed when the Civil War increased the desirability of an unbroken railway between the nation's capital and the northeast.³⁴

Parker completed the bridge in 1866 and then served as acting President of the railway before spending the next three years working as a consulting engineer on numerous long-span bridges. In 1870 Parker returned to Lancaster, eager to serve as the President of a new railway company, the Lancaster Railroad, formed by a group of local businessmen from Lancaster, Bolton, Acton and Stow. Strong competition and under-financing soon brought the railroad to bankruptcy. The disgruntled bridge committee member, C.L. Wilder, served on

PONAKIN BRIDGE
HAER No. MA-13
(page 11)

the Board of Directors of the railway, and the ultimate failure of the venture might have explained his objection to Parker's election to the bridge committee.³⁵

The connection between Parker, a skilled engineer and expert in long-span railway bridges--and the Post truss, with which he would have certainly been familiar--is an obvious one, but no other evidence has been found to directly connect Parker to either Simeon Post or the Post truss. Perhaps Parker felt that the Atherton Bridge was an inferior knock-off of the Post truss, and hoped to make a point by buying Lancaster's new trusses from the licensed builder. The possible dissension between Parker and Wilder, the aborted attempt to start a new railway company, and the coincidence of two Post-type trusses in one small town in New England would seem to offer at least some circumstantial evidence that the three interrelated.

Whether or not Parker had in mind a Post truss when he accepted the bridge committee position may never be known, but the town treasurer's ledgers showed that in the spring of 1871 the bridge committee advertised for bridge proposals in the Boston Daily Advertiser. Sometime later that summer, the town officials contracted with the Watson Manufacturing Company of Paterson, New Jersey, to build two 100-foot Post trusses, one at Center Bridge near Lancaster Center, and the other at Ponakin Bridge, each at a cost of \$3,570.³⁶

Construction of the Ponakin Bridge

Local farmers helped tear down the old bridge, and the town paid local masons to prepare the stone abutments at Ponakin before the bridge arrived by railroad. Work commenced on the foundations in early August and the bridges arrived by railroad in November. Some bridge firms supplied their own erection crews, but the amount of paid labor on the Ponakin Bridge project suggests that the town also enlisted local men to help build the falsework and erect the bridge, continuing traditional practices of local self-help under the direction of the engineer sent by the bridge manufacturer.

On December 2, 1871, the newspaper reported that two "S.S. Post's iron and combination bridges, built by the Watson Manufacturing Company of Paterson, New Jersey, 102 feet length between the abutments, 97 feet at top and 96 feet at bottom; clear in roadway 20 feet, height 15 feet," had been completed. The bridge committee hired Joshua Thistle, an engineer from the Lancaster Mills, to test the structural safety of the bridges. Using a loaded wagon, Thistle measured a deflection of .037' with a weight of 14 tons and 612 pounds. The total cost paid by the town for the Ponakin Bridge amounted to \$5,981.21.³⁷

Preservation of Lancaster's Post-Truss Bridges

Although the Ponakin and Atherton Bridges show signs of age and deterioration, they have been altered only slightly since their erection in 1871 and 1870. The town records show that approximately every ten years, and sometimes more or less frequently, workmen replaced the wood deck and stringers or performed some minor maintenance on the trusses, such as painting the iron work.

PONAKIN BRIDGE
HAER No. MA-13
(page 12)

The greatest threat to the iron trusses has always been obsolescence. As early as 1910, Lancaster's road commissioners advocated replacing the town's iron bridges with wider concrete-arch highway bridges for safety and durability. Fast-moving automobiles could not pass the narrow bridges safely, and heavily-loaded trucks and buses placed stresses on the trusses that the builders rarely had designed them to carry. Over the decades, Lancaster's iron bridges slowly disappeared, casualties of metal fatigue, unsafe conditions, or floods. The Atherton and Ponakin Bridges survived simply because the closing of the mills and the completion of the state highways relegated them to less-traveled backroads.³⁸

Nonetheless, in the 1970s heavy traffic finally took its toll. In 1973, the town requested funds from the state to replace the Atherton Bridge, and shortly thereafter closed the bridge to vehicular and pedestrian traffic. This aroused minor complaints of inconvenience from local residents, but eventually they found other ways around the river crossing.

In 1977 the Massachusetts Department of Public Works (MDPW) signed contracts to replace the bridge, but the request met with some local resistance. Some favored a new bridge, but others had grown to like the quiet dead end street created by the bridge barriers. The historical significance of the Atherton Bridge was only dimly understood by most members of the community. In the meantime, the engineers had also closed the Ponakin Bridge, adding it to the threatened structures list.

Fortunately for the bridges, Lancaster had an active preservation movement. The town center included a beautifully restored Bullfinch meeting house, a town green, neoclassical library, and numerous examples of eighteenth- and nineteenth-century domestic architecture. A group of citizens led by Bill Farnsworth, a town selectman, and Phyllis Farnsworth, chairperson of the Lancaster Historical Commission (LHC), wondered if the bridges could be saved. Phyllis Farnsworth wrote an article for the paper pointing out that the Atherton Bridge was Lancaster's first iron truss.³⁹ The LHC became aware of the bridges' national significance when an inquiry to the Historic American Engineering Record brought a letter from Douglass L. Griffin, HAER Historian, who wrote back that "Taken together, the [Atherton and Ponakin Bridges] comprise a unique pair of structures representing an important aspect of American's engineering heritage, and HAER encourages your efforts to nominate them to the National Register of Historic Places." After receiving HAER's letter, Phyllis Farnsworth began an aggressive campaign of publicizing the bridge's historic significance and contacted Lancaster's congressman for assistance.⁴⁰

In a stroke of good luck, an incomplete federal flood study of the Nashua River temporarily halted the replacement of the Atherton Bridge in 1978. This allowed the Historical Commission time to apply for, and receive, National Register certification on both the bridges, thus barring the MDPW from using federal funds to demolish the bridges, and bringing the replacement project to a halt. Some members of the community hailed this action, but others disdained the further inconvenience created by closed bridges.

The controversy over Lancaster's Post trusses has attracted the attention of amateur and professional historians, engineers, and industrial archaeologists. Since the late 1970s, a number of reports and studies have been made. In early 1981, students from Worcester Polytechnic Institute

PONAKIN BRIDGE
HAER No. MA-13
(page 13)

completed two projects, the first reviewing the Ponakin bridge's structure and history, and the second developing a public promotion plan for Lancaster bridge preservation. A scenic greenway along the Nashua River is also on the drawing table, and the bridges might be incorporated in a bike and walking path. In 1988, the Lancaster Historical Commission accepted responsibility for the care and maintenance of the Atherton Bridge from the MDPW. Barring misfortune or neglect, Lancaster's Post trusses may survive another century or more.⁴¹







PLATE XXVI
TRANS. AM. SOC. CIV. ENGRS.
VOL. XXII, NO. 418.
COOPER ON
AMERICAN RAILROAD BRIDGES

Side Elevation Span 200 Feet.


POST'S PATENT DIAGONAL TRUSS IRON BRIDGE.



Connections of Lower Chord at A.



Connections of Top Chord.



Forward End Post and Compensation for Expansion.

FIGURE 1: Diagram of a Post Truss.
(T. Cooper, "American Railroad Bridges," 1889.)

PONAKIN BRIDGE
HAER No. MA-13
(page 14)



FIGURE 2: Ponakin Bridge at Ponakin Mill, ca.1900.
(Collection of the Lancaster Historical Commission.)

PONAKIN BRIDGE
HAER No. MA-13
(page 15)

This duty they have assumed, this the law imposes on them, and this those for whom they act have a right to expect. They are not permitted to watch over their own interests; they cannot speak in their own behalf; they must trust to the fidelity of their agents. If they discharge these important duties and trusts faithfully, the law interposes its shield for their protection and defence: if they depart from the line of their duty, and waste or take themselves, instead of protecting, the property and interests confided to them, the law, on the application of those thus wronged or despoiled, promptly steps in to apply the correction, and return to the injured what has been lost by the unfaithfulness of the agents.

This right of the *cestui que trust* to have the sale vacated and set aside, when his trustee is the purchaser, is not impaired or defeated by the circumstances that the trustee purchased for another. [Citing *ex parte Bennett*, 10 Ves. 386.] It follows, therefore, that if defendant Sherman was incapacitated to purchase for himself, he was equally incapacitated to act for the defendant Dean; and if Dean were sole purchaser, the purchase would be set aside.

Neither are the duties or obligations of a director or trustee altered from the circumstance that he is one of a number of directors or trustees, and that this circumstance diminishes his responsibility, or relieves him from any incapacity to deal with the property of his *cestui que trust*. The same principles apply to him as one of a number as if he were acting as a sole trustee.

[His Honor next proceeds to decide that the action of the stockholders at the meeting of June, 1867, in ratifying the dealings with Sherman and Dean, was not such a ratification as prevents the company from maintaining their suit; for the general reason that they had not knowledge of all facts. He then states the final conclusion to which he arrives.]

I have arrived at the conclusion, entirely clear to my own mind, that this deed and contract cannot be sustained.

I have arrived at the result without considering the question of fraud raised in the complaint and denied by the affidavits. I have chosen to place my decision on higher and more satisfactory grounds. For the reasons I have stated, the plaintiffs having established a *prima facie* right to have the deed and contract set aside and the lands sold reconveyed to them, it is my duty to restrain the defendants until the hearing of this cause, as asked for in the complaints and supplemental complaints.

The plaintiffs have the right to their real estate, or anything into which it has been transmuted.—It is, therefore, proposed to restrain the defendants from transferring the stock owned by them in the Hoffman Coal Company, which but represents the real estate of the plaintiffs, and the privileges and advantages secured by the transportation contracts.

The motion for injunction is therefore granted.

Pacific Railroad.

At the meeting of this company held in St. Louis on the 28th ult., the following gentlemen were elected Directors, viz: J. P. H. Gray, H. L. Patterson, James E. Yeatman, A. Meier, Geo. R. Taylor, Joseph Charles, Robert Campbell, Thomas Allen, Daniel R. Garrison, John M. Wimer, A. W. Glover, Robert Barth.

The report of the company made to the stockholders states that on the 4th of May last, there were 25 miles of new road opened from Jefferson City to California, in Montevideo county; and on the 25th of July following, 12½ miles additional of track was opened; making 37½ miles of new track added to the Pacific road during the year. In addition to this, 19 miles of track on the Southwest Branch, from Franklin to St. Clair station, has been opened. A length of six additional miles on the Southwest Branch is ready for the

rails, and will be opened in a few weeks. It is expected also that by the first of October next, the road will be opened to Jamestown, a distance of 104 miles from St. Louis.

The receipts of Transportation Department from opening of road to March 1, 1869, were.....\$2,006,824 02
Total expenses of Transportation Department to same date.....1,270,273 64

Cash balance.....\$736,550 48
—which sum has been applied to the payment of interest on State bonds, and has reduced the interest account on the books of the company to that amount.

It is estimated that it will require \$3,250,000 to complete the road to Kansas City.

TREATISE ON THE PRINCIPLES OF CIVIL ENGINEERING AS APPLIED TO THE CONSTRUCTION OF WOODEN BRIDGES.

By S. S. Post, Civil Engineer,
And late Chief Engineer of the N. Y. & Erie R. R.

§ 1. Force is an agency which, applied to a load, tends to impart motion to it, or to retard it, or to bring it to a state of rest.

§ 2. When two or more forces acting upon a body neutralize each other, the result is an equilibrium, called pressure.

§ 3. Two weights or pressures are equal when one may be substituted for another with similar results.


§ 4. If two or more forces act upon the same point, their united effect is called the resultant of these forces.

§ 5. The several forces, whose combined effect is equivalent to a single force are called the components of that force.

§ 6. The resultant is mechanically equal to its components, and can be substituted therefor; or, the components for the resultant, without change of condition.

This proposition may be illustrated as follows:


Fig. 1.



1. Let a fine line be passed over two pulleys (a and b) fixed against a vertical plane or wall, and let known weights (A and B) be attached to the ends of the line. At some point (D) in this line, between the pulleys, knot another line with a third weight (C) attached. If the weight C be less than the sum of the other weights (A and B) the knot will assume a certain position (D), and it will be found to return to the same point as often as the experiment shall be tried, unless some one or more of the weights be changed.

According to the foregoing definitions the weights (A, B and C) are in equilibrium. A and B, as components, act upon the point D, with the same effect as their resultant C. But, the force A is equally the resultant of B and C, as components: and B may, also, be considered the resultant of A and C.


Fig. 2.



b. If a rod be fixed vertically between the point D and the ceiling—or some other immovable object (O), then by removing the weight C the point D remains in the same position as before.

The pressure upon the rod will be equal to the weight C removed, and is the resultant of the weights A and B.


Fig. 3.



c. The point D, instead of being supported by weights, acting in the direction Da and Db, may be sustained by rods or struts (DF and DH), pressing against it. The same weight (C) being suspended from the point D, the rod DF will sustain a force equal to that which was in the former case exerted by the weight B in the direction Db; and DH a force equal to that which was exerted by the weight A in the direction Da.

§ 7. If three forces act upon one point, and keep it at rest, then those three forces are proportional to the three sides of a triangle, to which sides, also, the directions in which they act are parallel.

Fig. 4.



UNITED STATES PATENT OFFICE.

SIMON S. POST, OF JERSEY CITY, NEW JERSEY.

IMPROVEMENT IN IRON BRIDGES.

Specification forming part of Letters Patent No. 22,919, dated June 16, 1863.

To all whom it may concern:

Be it known that I, S. S. Post, of Jersey City, county of Hudson, State of New Jersey, have invented a new and Improved Method of Constructing Iron Bridges; and I do hereby declare that the following is a full and exact description thereof, reference being had to the accompanying drawings and the letters of reference marked thereon.

The nature of my invention consists in constructing an iron bridge in such a manner as that the expansion and contraction of the material will not produce injurious effects upon the structure, and in this manner obviating one of the most serious objections to the universal use of such bridges.

To enable others skilled in the art to make and use my invention, I will proceed to describe its construction more minutely.

Figure 1 shows a side elevation of two panels of one end of a truss or girder. Fig. 2 shows a plan of the chord and its attachments. Fig. 3 shows an end view of a post with the attachment of the chord and top plate. Fig. 4 shows a side view of a post. Fig. 5 shows a plan of the upper plate or chord used by me.

I fasten the pedestal A by means of suitable bolts to the masonry or proper abutment, which pedestal is made to receive the end post of the bridge, which post is rounded at the bottom, as shown at B, and held in the pedestal (which has a lip, d) by the bolt g, passing through both the pedestal and the slot e in the chord F, to which chord I attach the brace g, which is fastened with the strut or post H to the top chord or plate, J, by means

of a bolt, k, passing through the joint box L, as shown in Fig. 3, k. The joint-box is used for the purpose of connecting the sections of the top chord or plate in such a manner that by passing the bolt k through the struts and braces will allow both to revolve upon said bolt to an extent corresponding to the degree of the expansion or contraction. The joint-box may be placed upon the struts, and the braces g' and h' may be introduced, as shown in Fig. 3, at R, and the bolt k passed through, as shown in Fig. 1 at P, after which the sections of the plate or upper chord may be attached to the box by bolts in m.


Having thus described my invention, what I claim, and for which I desire to secure Letters Patent, is—

1. The joint box connecting segments of the top chord or plate, and also receiving the heads of the posts or struts and braces, with the loose pin k passing through the whole.
2. A cylindrical joint in the construction of a bridge, as shown at B, irrespective of its location, when used for the purpose of obviating the dangers of expansion and contraction.
3. The slotted chord, when used in connection with the cylindrical joint and for the same purposes.
4. The construction of the chord, when used in combination with the cylindrical joint, substantially as described and shown.

S. S. POST.

Witnesses:

ANDREW J. POST,
O. A. STEVENS.



PONAKIN BRIDGE
HAER No. MA-13
(page 17)

PONAKIN BRIDGE
HAER No. MA-13
(page 18)





FIGURE 3: Union Pacific Railroad Bridge, Omaha, Nebraska.
(Condit, American Building Art, 1960, p. 147.)



PONAKIN BRIDGE
HAER No. MA-13
(page 19)

ENDNOTES

1. Carl W. Condit, American Building Art: The Nineteenth Century (New York: Oxford University Press, 1960), pp. 145-46.
2. The author has heard of only two other surviving Post trusses: the Bell's Ford Bridge in Seymour, Indiana, and another bridge in Newark, Ohio. Committee on History and Heritage of American Civil Engineering, "American Wooden Bridges," (New York: American Society of Civil Engineers, 1976).
3. The authority for the classic Post truss is an illustration from Theodore Cooper, "American Railroad Bridges," Transactions of the American Society of Civil Engineers, vol. 21 (1889), plate 26. The Atherton Bridge differs in so many ways from the classic design, that a case could be made that it is not a Post truss, but an extremely unusual hybrid truss form. Nevertheless, historically the Atherton Bridge has been described as best resembling a Post truss, and will be treated as such in this report.
4. "Memorial to Simeon S. Post," Proceedings of the American Society of Civil Engineers, vol. 19 (1893), pp. 49-50.
5. William H. Wisely, The American Civil Engineer, 1852-1974: The History, Traditions, and Development of the ASCE (New York: American Society of Civil Engineers, 1974), pp. 77-79.
6. Condit, pp. 103-124.
7. Ibid., pp. 109-118.
8. Ibid., p. 107.
9. "Memorial to Simeon S. Post," p. 49.
10. Daniel H. Calhoun, The American Civil Engineer, Origins and Conflict (Cambridge, 1960), pp. 4-30; "Memorial to Simeon S. Post," p. 49; and, Wisely, pp. 14-18.
11. Even though Whipple's book had been published over a decade earlier, it still had not made much impact upon bridge builders. Simeon S. Post, "Treatise on the Principles of Civil Engineering as Applied to the Construction of Wooden Bridges," American Railroad Journal, vol. 15 (April-November 1859), pp. 226-29, 243-45, 258-61, 274-76, 290-92, 308-10, 323-25, 340-43, 358-59, 372-73, 389-91, 405-06, and 421-23.
12. Victor Darnell, Directory of American Bridge Building Companies, 1840-1900 (Washington, DC: Society for Industrial Archeology, 1984), pp. vii-ix.
13. Post's patent drawings closely match the configuration of joints at the Ponakin Bridge. Simeon S. Post, "U.S. Patent No. 38,910," June 16, 1863.

PONAKIN BRIDGE
HAER No. MA-13
(page 20)

14. "Memorial to Simeon S. Post," p. 50.
15. Ibid.
16. Condit, pp. 145-46.
17. Ibid.; and, Tyrrell, pp. 175-76. Whether Post, or firms licensed by Post, built these bridges is unknown. Research in the Midwest would be necessary in order to build a fuller picture of the history of the Post truss.
18. A good introduction to nineteenth-century trusses can be found in: T. Allan Comp and Donald Jackson, Bridge Truss Types: A Guide to Dating and Identifying, Technical Leaflet 95, American Association for State and Local History, May 1977.
19. Col. William E. Merrill, Iron Truss Bridges for Railroads: Methods of Calculating Strains with a Comparison of the Most Prominent Truss Bridges, and new Formulas for Bridge Computations; also, the Economical Angles for Struts and Ties (D. Van Nostrand, 1870), pp. 85-92, and 128-30.
20. Squire Whipple, "On Truss Bridge Building," Transactions of the American Society of Civil Engineers, vol. 1 (1872), pp. 239-44.
21. As part of their senior thesis on the Ponakin and Atherton Bridges, Gregory P. Stanford and Michael A. Thompson (Worcester Polytechnic Institute) claimed that their structural analysis of the Ponakin Bridge probably proves that Post had economy of material in mind when he inclined the truss's posts. However, without further evidence, this assertion cannot be verified. Gregory P. Stanford and Michael A. Thompson, "Structural and Historic Aspects of Post Patent Trusses in Lancaster, Massachusetts," Senior Thesis, Worcester Polytechnic Institute, May 20, 1981.
22. Photocopies of photographs in a letter from Douglass L. Griffin (HAER) to Phyllis Farnsworth, July 26, 1978, Ponakin Bridge file, Lancaster Historical Commission, Lancaster, Massachusetts.
23. J.A.L. Waddell, Bridge Engineering (New York: John Wiley & Son, 1916), p. 347; Darnell, p. 33; Condit, pp. 145-50; and, Comp and Jackson, p. 3.
24. George Fillmore Swain, Structural Engineering: Stresses, Graphical Statics, and Masonry (1927), p. 129.
25. Abijah P. Marvin, History of the Town of Lancaster, 1650-1879 (Lancaster, Massachusetts: Town of Lancaster, 1879).
26. Ibid.
27. Ibid., pp. 442-43.
28. Ibid., pp. 441-50.

PONAKIN BRIDGE
HAER No. MA-13
(page 21)

29. Town Reports, various years, 1821-1866.
30. Lancaster League of Historical Societies, Towns of the Nashaway Plantation (Lancaster, Massachusetts: Lancaster League of Historical Societies, 1976), pp. 194-97; Andrew E. Ford, History of the Origin of the Town of Clinton, 1653-1865 (Clinton, 1896); and, "Ponakin Mills Closed 1927," Ponakin Mills File #919, Lancaster Historical Commission.
31. "Nathaniel Thayer," Dictionary of American Biography, Vol. IX (New York: Charles Scribner & Sons, 1935), pp. 409-10; and, Dr. J.L.S. Thompson, personal journal, p. 91, Lancaster Historical Commission Collection.
32. J.L.S. Thompson, personal journal, p. 91.
33. Clinton Courant, April 8, 1871.
34. "Memorial to George Alanson Parker," Journal of the Association of Engineering Societies, vol. 8 (1887), pp. 334-38.
35. Ibid.; and, Clinton Courant, Oct. 1, 1870.
36. A flood washed away the Center Bridge in 1935.
37. Clinton Courant, Aug. 5 and Dec. 2, 1871; and, Town Reports, 1871, pp. 10-11.
38. Town Reports, 1910, p. 38.
39. Kathleen Shaw, "New Bridge Waits as Planners Work," Worcester Telegram, Aug. 26, 1980; Phyllis Farnsworth, "Atherton Bridge Threatened," Clinton Daily Item, Sept. 3, 1977; and, Ponakin and Atherton Bridge files, Lancaster Historical Commission.
40. Douglass L. Griffin to Phyllis Farnsworth, July 26, 1978, Atherton and Ponakin Bridge files, Lancaster Historical Commission.
41. Phyllis Farnsworth to Ellen Digerinimo, November 3, 1988, Atherton Bridge files, Lancaster Historical Commission.

PONAKIN BRIDGE
HAER No. MA-13
(page 22)

BIBLIOGRAPHY

- "Atherton Bridge," clipping and photo file, Lancaster Historical Society, Lancaster, Massachusetts.
- Calhoun, Daniel H. The American Civil Engineer, Origins and Conflict. Cambridge, Massachusetts, 1960, pp. 4-30.
- Clinton Courant, Clinton, Massachusetts, 1870-1871.
- Committee on History and Heritage of American Civil Engineering. "American Wooden Bridges." New York: American Society of Civil Engineers, 1976.
- Comp, T. Allen and Donald Jackson. Bridge Truss Types: A Guide to Dating and Identifying, Technical Leaflet 95, American Association for State and Local History, 1977.
- Condit, Carl W. American Building Art: The Nineteenth Century. New York: Oxford University Press, 1960.
- Cooper, Theodore. "American Railroad Bridges," Transactions of the American Society of Civil Engineers, vol. 21 (1889), plate 26, figure 1.
- Darnell, Victor. Directory of American Bridge Building Companies, 1840-1900. Washington, DC: Society for Industrial Archaeology, 1984.
- Lancaster League of Historical Societies. Towns of the Nashaway Plantation. Lancaster, Massachusetts: Lancaster League of Historical Societies, 1976, pp. 194-97.
- Marvin, Abijah P. History of the Town of Lancaster, 1650-1879. Lancaster, Massachusetts: Town of Lancaster, 1879.
- "Memorial to Simeon S. Post," Proceedings of the American Society of Civil Engineers, vol. 19 (1893), pp. 49-50.
- Merrill, Col. William E. Iron Truss Bridges for Railroads: Methods of Calculating Strains with a Comparison of the Most Prominent Truss Bridges, and New Formulas for Bridge Computations; also, the Economical Angles for Struts and Ties. D. Van Nostrand, 1870, pp. 85-92, 128-30.
- "Nathaniel Thayer," Dictionary of American Biography, vol. IX. New York: Charles Scribner & Sons, 1935, pp. 409-10.
- "Ponakin Bridge," clipping and photo file, Lancaster Historical Society, Lancaster, Massachusetts.

PONAKIN BRIDGE
HAER No. MA-13
(page 23)

- Post, Simeon S. "Treatise on the Principles of Civil Engineering as Applied to the Construction of Wooden Bridges," American Railroad Journal, vol. 15 (April-November 1859), pp. 226-29, 243-45, 258-61, 274-76, 290-92, 308-10, 323-25, 340-43, 358-59, 372-73, 389-91, 405-06, 421-23.
- Post, Simeon S. "U.S. Patent No. 38,910," June 16, 1863.
- Stanford, Gregory P. and Michael A. Thompson. "Structural and Historic Aspects of Post Patent Trusses in Lancaster, Massachusetts," Senior Thesis, Worcester Polytechnic Institute, Worcester, Massachusetts, May 20, 1981.
- Thompson, J.L.S. Private journal. Collection of Lancaster Historical Society, Lancaster, Massachusetts.
- Town of Lancaster, Massachusetts. Annual Reports, 1821-1871.
- Tyrrell, Henry Grattan. History of Bridge Engineering. Chicago: H.G. Tyrrell, 1911.
- Waddell, J.A.L. The Designing of Ordinary Iron Highway Bridges. New York: John Wiley & Sons, 1884.
- Whipple, Squire. "On Truss Bridge Building," Transactions of the American Society of Civil Engineers, vol. 1 (1872), pp. 239-44.
- Wisely, William H. The American Civil Engineer, 1854-1974: The History, Traditions, and Development of the ASCE. New York: American Society of Civil Engineers, 1974.

HAER No. MA-13

HISTORIC AMERICAN ENGINEERING RECORD

INDEX TO PHOTOGRAPHS

Ponakin Road Bridge
Spanning North Branch of Nashua River
on Ponakin Road
Lancaster Vicinity, Massachusetts
Worcester County

Jet Lowe, Photographer 1979

MA-13-1	"BARREL SHOT" SHOWING TRUSS AND WOODEN DECK
MA-13-2	GENERAL VIEW SHOWING TRUSS AND MASONRY ABUTMENTS, LOOKING DOWNSTREAM
MA-13-3	DETAIL OF CENTER PANEL POINT WHERE INCLINED COMPRESSION MEMBERS MEET
MA-13-4	DETAIL OF TOP CHORD PORTAL CONNECTION

HISTORIC AMERICAN ENGINEERING RECORD

INDEX TO PHOTOGRAPHS

Addendum to
Ponakin Bridge
Spanning the Nashua River on Ponakin Road
Lancaster
Worcester County
Massachusetts

HAER No. MA-13

Martin Stupich, Photographer, Summer 1990

Photographs MA-13-1 through MA-13-4 were previously transmitted to the Library of Congress.

- MA-13-5 General view of east portal from cherry picker, looking northwest
- MA-13-6 General view of east portal elevation, looking west
- MA-13-7 General view from center of span, looking toward east portal
- MA-13-8 East portal from deck, looking east
- MA-13-9 Southeast endpost, looking south
- MA-13-10 General view of north truss from deck, looking east
- MA-13-11 Detail of north truss, showing center "A" configuration of members, looking north
- MA-13-12 Detail of N-8, showing flattened rivet
- MA-13-13 Endpost detail, showing connection with top chord and diagonals
- MA-13-14 Detail of top chord (north truss, near west end) at N-U-4, showing cast joint cap over post
- MA-13-15 Detail of bottom chord of south truss, showing lower connections
- MA-13-16 Bearing shoe, southwest corner, showing pin through eyebar with intact nuts
- MA-13-17 Underside of deck, looking west, showing beams and cross-bracing
- MA-13-18 Detail of floor beam connection to bottom chord, south truss, east end
- MA-13-19 Abutment at southeast corner

LAN.900

HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-1



LAN.900

HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-2



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-3



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-4



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-5



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-6



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-7



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-8



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-9



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-10



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-11



LAN.900

HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-12



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-13



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-14



LAN.900

HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-15




HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-16



HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-17




HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-18




HISTORIC AMERICAN ENGINEERING RECORD
SEE INDEX TO PHOTOGRAPHS FOR CAPTIONS

HAER No. MA-13-19




PONAKIN BRIDGE · 1871

LANCASTER, MASSACHUSETTS



Scale: $3/16\" = 1' - 0\"$



The Massachusetts Historic Bridge Project is part of the Historic American Engineering Record (HAER) a long-range program to document historically significant engineering and industrial sites in the United States. The National Park Service U.S. Department of the Interior administers the HAER program. The Massachusetts Department of Public Works, Jane F. Garvey, Commissioner, George R. Turner, Jr., Chief Engineer, and Stephen J. Roper, Historic Bridge Specialist; and the Historic American Engineering Record (HAER), Dr. Robert J. Kapsch, Director, co-sponsored the Massachusetts Historic Bridge Project with the cooperation of the Massachusetts Historical Commission, Elsa Fitzgerald, Acting Exec. Dir. The field team under the direction of Eric DeLony, Chief and Principal Architect, HAER, consisted of Daniel L. Schadek, professor of architectural technology (Harvard University), field supervisor, Patricia Reese (Boston Architectural Center), Gary Kleinschmidt (Harvard University), Chris Payne (Columbia University), Morgan Fleisig (Harvard University), Mark Rowan (Catholic University of America), and Rudolf Sosel (Technical University of Delft, the Netherlands, US/ICOMOS), architectural technicians; Lola Bennett (University of Vermont), Patrick Harshbarger (University of Delaware/Hagley Museum and Library), and John Healey (University of Birmingham, England, US/ICOMOS), historians; and Marty Stupich (Massachusetts College of Art), photographer.

The Ponakin Bridge (1871) is the only known surviving iron bridge to incorporate all of the design features of Simeon S. Post's Patent Diagonal Truss Bridge. Post trusses enjoyed a brief period of popularity in the late 1860s and early 1870s. Railroads often chose Post's bridge for long-span river crossings. The Ponakin Bridge is an unusual example of a Post truss used for a relatively short-span highway bridge.

The Ponakin Bridge has joints that match the drawings of Post's patent (No. 38,910), granted in 1863. A special cast-iron joint box connects the top chord to the posts, struts, and braces; the bottom of the end posts are rounded and fit into cylindrical joints where they meet the bottom chord; and, a pin passes through a slot in the bottom chord to tie the end posts to the chord. Post claimed that these joints allowed the bridge to expand and contract without injury to its structure.


Although Post patented his joints, he never patented the unique combination of posts and diagonals that became the signature of his bridges. The Ponakin Bridge bears the Post truss's hallmark of cast-iron posts that incline towards the center of the bridge and double-intersecting, wrought-iron diagonals that incline toward the abutments. This through truss also has the characteristic upper and lower lateral bracing, and counters with adjustable turnbuckles.

The Watson Manufacturing Company of Paterson, New Jersey built the 100-foot long, 20-foot wide, single-span Ponakin Bridge. The firm held the license for Post's patented trusses, and Andrew J. Post, Simon S. Post's son, worked for the bridge manufacturer. The company probably built most of the iron Post trusses erected in this country.


The Ponakin Bridge replaced a series of wooden bridges that had crossed the North Nashua River at the village of Ponakin since the eighteenth century. The new iron truss served a small cotton textile village on the west bank until the factory closed in the early 1930s. The Ponakin Road remained the major thoroughfare between Lancaster and Lunenburg until 1965 when Route 117 bypassed the bridge. In 1978 the town closed the Ponakin Bridge after engineers discovered structural weaknesses.

The Ponakin Bridge has not been significantly altered, although it has sustained some damage; the lower chord has buckled. Fewer than five Post-type trusses are known to survive in the United States. In 1979 the National Register of Historic Places listed the Ponakin Bridge.

East Elevation




State Map



Local Map

UTM 19.279250.4705490
Based on U.S.G.S. 7.5 x 15 min. series
topographic map, Hudson Quadrangle,
1980 (edited 1988).

Scale: 1:16250



ILLUSTRATED BY PAUL REESE, 1990

MASSACHUSETTS HISTORIC BRIDGE PROJECT

LANCASTER

PONAKIN BRIDGE - 1871

Spanning the North Nashua River on Ponakin Road

WORCESTER COUNTY

MASSACHUSETTS

SHEET


1 of 6

HISTORIC AMERICAN
ENGINEERING RECORD

MA - 13

APPROVED PLEASE CREDIT: HISTORIC AMERICAN ENGINEERING RECORD, NATIONAL PARK SERVICE, NAME OF DILATOR, DATE OF THE DRAWING

Elevation



Plan



scale $3/8" = 1'-0"$ 

Table of Member Sections

Scale: $1/2" = 1'-0"$ 









Upper Lateral Strut








Upper Lateral Rod



Upper Chord

Post $U_0L_0(U_{10}L_{11})$ Main Diagonals U_0L_1, U_0L_2, U_1L_3
 $(U_5L_6, U_{10}L_9, U_{10}L_{10})$ Post $U_1L_1(U_9L_{10})$ Main Diagonals U_2L_4, U_3L_5
 (U_7L_6, U_8L_7) Post U_2L_2, U_3L_3
 (U_7L_8, U_8L_9) Counters U_1L_0, U_2L_1
 (U_6L_{10}, U_9L_{11}) Post U_4L_4, U_5L_5
 $(U_9L_6, U_{10}L_7)$ Counters $U_3L_2, U_4L_3, U_5L_4, U_6L_5$
 $(U_6L_5, U_7L_6, U_8L_7, U_9L_8)$ 

Lower Chord




Floor Beam







Lower Lateral Rods







Connections of Lower Chord

Scale: 6" = 1'-0" (Isometric)



Elevation L4

Scale: 4" = 1'-0"



Section L4

DRAWN BY PAT REESE, 1990

MASSACHUSETTS HISTORIC BRIDGE PROJECT

UNIVERSITY OF MASSACHUSETTS SYSTEM

LANCASTER

PONAKIN BRIDGE - 1871
Spanning the North Nazareth River on Pawtucket Road
WORCESTER COUNTY


MASSACHUSETTS

SHEET 4-6

HISTORIC AMERICAN
ENGINEERING RECORD
MA - 13




BY REPRODUCER PLEASE CREDIT HISTORIC AMERICAN ENGINEERING RECORD, NATIONAL PARK SERVICE, NAME OF DEDICATOR, DATE OF THE DRAWING

STRUCTURAL BEHAVIOR OF POST TRUSSES




Trusses carry all loads to the supports. Tension or compression forces are consequently induced in truss members. The member configuration shown is entirely characteristic of other Post trusses.

The rigid portals at both ends, along with the stiffening provided by the upper cross members at panel points, prevent the bridge from rocking sideways due to wind or other laterally acting forces.




The crossed diagonals in the planes of the top and bottom chords prevent the bridge from deflecting sideways due to wind (or other laterally acting forces) as well as helping to prevent torsional deformations.



Top chord members are in compression under full or partial loadings, with maximum forces normally developed in members at midspan. Rigid members are used to provide resistance to buckling.

Patent drawings for Post trusses show an abutment connection housing a slotted lower chord end which would allow free thermal expansion and contraction to occur.




FORCES IN TRUSS MEMBERS: FULL LOADING CONDITION

Loadings on the bridge include both "Dead Loads" and "Live Loads". Dead loads include the self-weights of the trusses, beams, and decking, and are always present. Live loads reflect the weights of vehicles and pedestrians and may or may not be present (the bridge may be only partially loaded with live loads as a vehicle moves across a bridge). A full loading condition with the maximum live and dead loading present is shown.

When a truss is loaded, tension or compression forces of varying magnitudes are developed in different truss members. These forces could be accurately predicted by 19th century engineers through a variety of analytical methods based on a mathematical understanding of the equilibrium of different joints in the truss, and subsequently used to determine the size and shape of truss members.

Upper chord members are always in compression. The largest forces occur at midspan and decrease towards the ends.

This width graphically reflects the magnitude of the force present.



Lower chord members are always in tension. The largest forces occur at midspan and decrease towards the ends.

Typical load concentrated at panel point.

Diagonals inclined towards midspan (the "posts") are in compression, while those oppositely inclined are in tension. The largest forces in these members occur at the ends and decrease towards midspan.

No forces exist in the counters.

— Compression Forces
— Tensile Forces
--- Counters

TRUSS MEMBERS: OTHER LOADING CONDITIONS

When vehicles or other loads move across the bridge (creating a nonuniform loading condition), the force types and magnitudes present in truss members changes. Only one of many possible partial loading conditions that could exist is shown below.

Stress-reversals may occur in some truss members. Compression forces may begin to develop in slender diagonal members designed primarily to carry tension forces only (these members buckle harmlessly out of the way as long as counters are present which go into tension and stabilize the truss). In some loading conditions, minor compression forces can develop in the lower chord members adjacent to the end supports (e.g., due to the braking action of vehicles, longitudinal earthquake or wind forces, or a failure of the expansion joint).

The forces in these members change from tension to compression, so the members buckle harmlessly out of the way.



The counters, which previously carried no forces, go into tension to stabilize the truss.

This member goes into tension.

Compressive forces can potentially develop in these members due to longitudinally-acting loadings.

The magnitudes of the forces in the truss members have changed.


MEMBER DESIGN

Members in the Ponakin Bridge have been sized and shaped in direct response to the nature and type of forces present. Members that have been designed to resist tension forces only are usually relatively slender and have small cross-sections. Members that have been designed to resist compression, and are hence susceptible to buckling, are always larger and stiffer.

There are small but obvious size differences in many of the truss members used in the Ponakin Bridge. These size differences reflect the variation in type and magnitude of forces in the truss as described to the left. These variations are diagrammed below and noted in detail in the Table of Member Sections (Sheet 2 of 6). Some variations, however, are associated with partial loading conditions described in the lower left figure.

Diagram of Member Types and Sizes Required

Required upper chord member sizes increase towards midspan. Rigid members must be used.



Required tension diagonal sizes increase towards the ends.
Required compression diagonal sizes increase towards the ends.

Actual Member Sizes Used in Bridge


Member size is based on maximum force present at midspan and is used throughout the length of the upper chord for fabrication ease.

Maximum size of lower tension chord member is at midspan. Tension diagonals and compression diagonals are largest toward the ends. Counters are smaller and of a constant size.

These are primarily slender tension members but have cross-ribs that provide some additional stiffening to carry minor compressive forces.

CAMBER

Excessive downward deflections were often problematic in 19th century bridges. The Ponakin Bridge was apparently designed with an upward camber to counteract these adverse deflections. The bridge tends to level out when subjected to a downward load. Levels taken on the bridge indicate that an upward camber still exists.



The final height at midspan of bridge relative to supports under full dead load. Original camber is upward resulting in the trusses being slightly arched.